## Independent Drive Re-alignment Project

Contract No: 71564-22 Client: City of Jacksonville

County: Duval

Construction Cost: \$2.3M Reference: Aaron Heric, P.E.

Project Manager (904) 255-8731 aheric@coj.net

## **Project Description**

This \$2.3M project consists of extending Independent Dr. due west from the roundabout at Laura St. to intersect with Hogan St. The design of this modification includes roadway design, traffic analysis, lighting, landscape, hardscape, geotechnical, and survey. Geotechnical effort includes 3 roadway borings at 10ft depth for establishment of existing pavement condition and development of pavement design for the re-aligned roadway. The project also includes MOT, erosion control, site preparation, demolition, and post design services.







Construction Engineering and Inspection Services 10250 Normandy Blvd., Suite 304 Jacksonville, FL 32221 (904) 783-9842