

MLK Water Main Replacement Project from Fairfax Street to Brentwood

JEA Project No.: 215597

Client: Jacksonville Electric Authority

County: Duval

Construction Cost: \$9.2M

Reference: David McDermet, P.E.

Project Manager

(904) 665-4626

mcdeds2@jea.com



Project Description

This project consists of 4,529 LF of CLDI 20" WM along W. 21st St. between Fairfax St. (WTP) and Abbott St. and I-95 and Brentwood Blvd., 1,729 LF of CLDI 16" WM along N. Myrtle Ave. between W. 22nd St. and W. 15th St., tie-ins to existing water mains along cross streets and fire hydrant laterals, 2,635 LF of 4" WM for water services along W. 21st St. by open cut, 875 LF HDPE 24" WM under MLK Pkwy by HDD, 205 LF of 30" steel casing by J&B under MLK Pkwy and Norfolk Southern Railroad at N. Myrtle Ave., removal and replacement of existing water services, installation of 25 new water services, abandonment of existing water mains by grout fill, removal and replacement of asphalt/concrete pavement, driveway, sidewalk, curb and gutter, and asphalt milling and resurfacing.



VIA^{CS}

- VIA CONSULTING SERVICES, INC. -

Construction Engineering and Inspection Services

10250 Normandy Blvd., Suite 304

Jacksonville, FL 32221

(904) 783-9842